

RENO COMPASS BLUEPRINT PLAN

Dossier ID: reno_s_f23e0f22c642048a8694d1c41e14f5e2

Generated At: 2026-07-07 00:02:18 UTC

Schema Version: 1.0.0

1. Project Summary

Project: Bathroom Remodel (bathroom_remodel)

Goal: switching the places of the vanity and toilet, and relocating the vanity's GFCI outlet to vanity new location

Property: Zip 95120, independent house, 50 sqft

Chosen design: economy (est. \$24,000-\$32,000)

2. Safety & Permit (review this first)

- Relocating the Toilet (Plumbing): TIER 2 PERMITTED (source: IRC P2705.1)
- Relocating the Vanity (Plumbing): TIER 2 PERMITTED (source: IRC P2705.1)
- Relocating the Vanity GFCI Outlet (Electrical): TIER 2 PERMITTED (source: (Matrix: "Swapping a GFCI receptacle or fixture on an existing adequate circuit = Tier-2/3 (not panel work)."))
- New Lighting Fixtures & Controls (including occupancy sensor): TIER 2 PERMITTED (source: (electrical work), California Title 24 (as discussed in Scope))
- New Flooring (Ceramic Tile or LVT): TIER 3 PROCEED (source: General construction practice (not in IRC/NEC permit triggers).)
- Drywall Repair and Painting: TIER 3 PROCEED (source: General construction practice (not in IRC/NEC permit triggers).)

Permits are required. Confirm the full scope with your local AHJ.

3. Budget

Target: \$40,000 Ceiling: \$45,000

Ballpark: \$13,950-\$21,700 (+ contingency \$2,162-\$3,364)

Reality check: plausible

All costs are estimated ranges - verify locally with real quotes.

4. Logistics & Displacement

Can live through it: True

Feasibility verdict: proceed

7. Advisory Checklist

- Itemized Bid: The quote should not be a lump sum. It must itemize all aspects of the work, including demolition, labor, and materials.
- Demolition & Debris Removal: Explicitly check for clear pricing for demolition down to the studs/slab, and for the removal and hauling away of all construction debris. This is a common silent omission.
- Plumbing Details: Ensure all plumbing work is broken down, specifying both labor and materials for rough-in, relocation of fixtures (vanity, toilet), and any necessary re-piping.
- Electrical Details: Similarly, electrical work should detail labor and materials for GFCI outlets, circuits, fan installation, and lighting (especially important for California's Title 24 compliance).
- Waterproofing System: This is critical for bathroom longevity. The quote must specify the waterproofing membrane and backer/cement board system to be used over all wet surfaces before tiling (e.g., specific brand names, sheet membrane or liquid-applied system). Its absence is a significant red flag.
- Fixture Specifications: Each new fixture (vanity, toilet, sink, faucet) should be listed with a specific model number and

price. This prevents last-minute substitutions with lower-grade products.

- Permit Line Item: There should be an explicit line item for all required permits (building, plumbing, electrical, mechanical). A contractor suggesting you skip permits is a major red flag, as unpermitted work can cause issues with resale, title, and insurance.
- Labor Rates/Hours: Ask for labor hours or rates by trade, which helps you sanity-check costs.
- Project Timeline: The quote should include a clear project timeline with a start date, estimated completion date, and key milestones, including when inspections will occur.
- Payment Schedule: Ensure the payment schedule is tied to the completion of specific project milestones, rather than requiring a large upfront payment or full payment before work begins.
- Warranty Terms: Clarify the warranty terms for both labor/craftsmanship and materials, and confirm who administers them (the contractor or the manufacturer).
- Change-Order Procedure: A clear, written process for documenting, pricing, and approving any changes to the scope of work before work proceeds is essential.
- License & Insurance: The contractor should provide their license number and proof of insurance and bonding. You should always verify these credentials with your state's contractor licensing board (e.g., California Contractors State License Board).

8. Phase Checklists

Before demolition:

- Order long-lead materials first.
- Confirm permits filed.

After demolition:

- Inspect for hidden conditions before closing walls.

While in progress:

- Keep waterproofing before tile.
- Hit inspection milestones.

Wrap-up:

- Final inspection sign-off before final payment.